


DO NOT SCALE. IF IN DOUBT ASK!

FB180 50mm: 60/30  
FB180 60mm: 90/60



90mm x 38mm MINIMUM THICKNESS TIMBER  
ALL TIMBER SUPPORTING OR ADJOINING THE FB180 ABLATIVE BATT INSTALLATION  
MUST BE PAINTED WITH FIREFLY® ABLATIVE COATING PRIOR TO INSTALLING THE ABLATIVE BATTS

FIREFLY® FB180 ABLATIVE BATT  
THE OUTER EDGES OF THE FB180 ABLATIVE BATT IS BUTTERED WITH FIREFLY® ABLATIVE COATING  
BEFORE BEING FRICTION FIT BETWEEN THE TIMBERS

ALL JOINTS BETWEEN ABLATIVE  
BATTS TO BE FINISHED WITH A 6mm  
BEAD OF FIREFLY® INTUMESCENT  
ACRYLIC, FLATTENED OVER THE JOINT

ALL JOINTS BETWEEN ABLATIVE BATTS  
AND TIMBERS TO BE FINISHED WITH A  
6mm BEAD OF FIREFLY® INTUMESCENT  
ACRYLIC



FIREFLY® FB180 ABLATIVE BATT CAN BE FRICTION FIT BETWEEN  
90mm x 38mm (MINIMUM THICKNESS) TIMBERS TO CREATE A WALL

FB180 ABLATIVE BATT CAN BE FIT IN EITHER ORIENTATION UP TO 4m VERTICALLY AND INDEFINITELY HORIZONTALLY  
AS LONG AS IT IS SUITABLY SUPPORTED BY THE TIMBERS

TIMBERS MUST BE PAINTED WITH FIREFLY® ABLATIVE COATING



All rights reserved. No parts of this drawing may be used reproduced, altered, stored in a retrieval system or transmitted in any form or by any means without the prior written permission of tba protective technologies ltd. Whilst every effort has been made to comply with the current statutory regulations, it is the user's responsibility to ensure that the final detailing and installation meets the requirements of relevant regulatory authority (often building control). Please check www.tbafirefly.com to ensure that you are using the correct and current version. Copyright © 2023

**FB180 ABLATIVE BATT - BATT WALL**

TBA PROTECTIVE TECHNOLOGIES LTD Unit 3, Transpennine Trading Estate, Gorrells Way Rochdale, OL11 2PX, United Kingdom T: +44 (0)1706 758 817 E: Technical@TBAFIREFLY.COM W: WWW.TBAFIREFLY.COM	DESIGNER: JC	DRAWING NO:
	APPROVED: KG	<b>B - 001</b>
	DATE: 11/03/2024	REVISION: 7
	SCALE: NTS	IN SEQUENCE: 1/1